



Office of the Councillors
BELDANGA MUNICIPALITY
P.O. BELDANGA, PIN-742133, DT. MURSHIDABAD
ESTD-1981

From :- Executive Officer



Phone & Fax: - 03482-264113

E-Mail ID :- beldanga.municipality@gmail.com &
chairmanbeldanga2010@gmail.com

Website :- www.beldangamunicipality.org

Memo No. 2784/II-1/22

Date 05/09/2022

Quotation Notice

Quotation are invited on behalf of Board of Councillors, Beldanga Municipality form "Construction of a Permanent hording /display board with supporting frame installed at ground.

The Terms and Conditions are as under

1. All Quotation shall have to reach to the office of the under signed within the specified time and date. The drop box is placed at the office chamber of the under signed.
2. Recoveries towards Govt. Taxes. Cess. GST will be deducted from the bill of the contractor on the basis of prevailing Govt. Rules.
3. Quotation will be accepted as per rules. However the undersigned reserves the right to accept or reject any or all quotation without assigning any reason what so ever.
4. Loading, Unloading and Carrying cost are to be borne by the supplier.
5. Last Date of submitting quotation : - 13.09.2022 (1 pm.)
6. Date of opening the quotation : - 13.09.2022 (2 pm.)
7. Date of Issuing Work Order :- 13.09.2022 (3 pm)
8. Date of Work to be completed within : - 30/09/2022 (within 4 pm.)

The rate and Total Amount for the above noted work are as Follows:-

Sl. No	Name of Work	Rate including All Taxes.
1	Construction of a Permanent hording /display board with supporting frame installed at ground.	

5.9.22

Executive Officer
Beldanga Municipality

Date- 05/09/22

Memo No- 2784(8)/II-1/22

For wide Publicity and information, copy forwarded to

1. The Chairperson, Beldanga Municipality
2. The Vice Chairman, Beldanga Municipality
3. The Finance Officer , Beldanga Municipality
4. The Representative Engineer , MED , Murshidabad with a request to remain present on opening date of the tender i.e. 13.09.2022 (2.00 Pm)
5. The Block Development Officer , Beldanga Block- 1 ,
6. The Station Master , Beldanga Rail Station , (www.municipalitybeldanga.org)
7. Notice Board, Beldanga Municipality.
8. IT Coordinator , Beldanga Municipality to upload the notice of Beldanga Municipal Website , (www.municipalitybeldanga.org)

5.9.22

Executive Officer
Beldanga Municipality

2370911/2022/IT SEC(SUDA)

Estimate of a permanent hording / display board with supporting frame installed at ground.

Rates have been taken from the P.W.D. Building SOR'2017 with latest Corrigenda for Saltlake Area

Sl No.	Ref.	Description of Item	Quantity	Unit	Rate	Amount
1	[P-1-2]	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. Depth of excavation not exceeding 1,500 mm.	0.648	%cum	11927.00	77.29
2	[P-47.1-3]	Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches.	0.720	sqm	24.00	17.28
3	[P-42.1-36(f)]	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) 25 mm to 30 mm shuttering without staging in foundation	3.640	sqm	209.00	760.76
4	[P-24.1-4]	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. Pakur Variety	0.385	cum	5317.93	2044.74
5	[P-101.1-2A]	M.S. structural works with hollow sections (square or rectangular shape) conforming to IS: 806-1968 & IS:1161-1998) connected to one another with bracket, gusset, cleat as per design, drawing & direction of Engineer-in-Charge complete including cutting to requisite shape & size, fabrication including metal arc welding conforming to IS: 816-1969 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of all M.S. Hollow section, all consumables such as electrodes, gas and hire charges of all tools and plants and labour required for execution and all incidental chages (such as electricity, labour insurance) etc. complete.				
		For other Structural works like galleries etc.	0.140	MT	74900.00	10490.34

2570911/2022/IT SEC(SUDA)

Sl No.	Ref.	Description of Item	Quantity	Unit	Rate	Amount
6	[P-200.1-1]	Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc	6.377	Sqm.	29.00	184.93
7	[P-200.1-2(A)(b)(iv)]	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : On steel or other metal surface : With super gloss (hi-gloss) - Two coats (with any shade except white)	4.217	Sqm.	79.00	333.13

Total 13908.48

Add GST @ 12% 1669.02

(A) Total including GST = 15577.49

Add Cess @1% on (A) = 155.77

(B) Total including Cess & GST = 15733.27

Add Contingency @3% on (A) = 467.32

Grand Total = 16200.59

Say Rs. 16201.00

(Rupees Sixteen thousand two hundred and one) only.

N.B.: 1) Lettering item to be added separately as per item no. 8.03 of Page no. - 269 of P.W.D. SOR for Roads & Bridge Work.

2) The estimate @Rs. 16,201.00 per unit is prepared for Saltlake area. Estimate for other ULBs should be prepared following the scheduled rate for respective district / town.

Shankar
08/07/22
Junior Engineer (Civil)
Planning Circle (South) M.E. Dte.,
Department of UD & M.A.,
Government of West Bengal

Aswini
08/07/22
Assistant Engineer (Civil)
Planning Circle (South) M.E. Dte.,
Department of UD & M.A.,
Government of West Bengal

J. Choudhury
8/7/22
Superintending Engineer
Planning Circle (South) M.E. Dte.,
Department of UD & M.A.,
Government of West Bengal