

# Office of the Board of Councillors BELDANGA MUNICIPALITY

P.O. BELDANGA, PIN-742133, DT. MURSHIDABAD

1981 . 1981 2 . 10. 1981

Phone & Fax: - Off. – 264113
E-Mail ID: - <u>beldanga.municipality@gmail.com</u>
Website: - www.municipalitybeldanga.org

Memo No. ... 26.96. 11-11.23. ...

Dated ... 23 08 23

### **Quotation Notice**

Sealed quotations are invited from the recognized agency having experience in similar type of works listed below under Beldanga Municipality.

#### List of Works

Sl.	Name of Work	Estimated
No.		Amount
1	Repairing of existing damaged drains at different wards within Beldanga Municipality.	95528.00
2	Repairing of Bituminous Road on emergency basis near flower mill of Lalu Ganai on Madda	97310.00
	bituminous road, ward no. 13 within Beldanga Municipality.	1

#### TERMS AND CONDITION ARE AS UNDER

- 1. The agency who agreed to participate in the quotation, will have to submit their rate in their letter head (as per the proforma annexed herewith) along with valid up to date certificate of GST Registration, Current GST return, P. Tax Challan, Valid Trade License, and PAN Card including copy of estimate signed by the participant. Agency who wants to participate more than one work, will have to submit their quotations separately for each work.
- 2. Payment will be made through Account payee cheque or online.
- 3. Tax will be deducted as per running rule.
- 4. The Prospective Bidder shall have to execute the work in such a manner so that appropriate service level of the work is maintained during progress of work and a period of 1 (one) year from the date of successful completion of the work to the entire satisfaction of the Engineer-in-Charge. If any defect / damage is found during the period as mentioned above, the contractor shall make the same good at his own cost to the specification at par with instant project work. On failure to do so, penal action against the contractor will be imposed by the Department as deem fit. The contractor may quote his rate considering the above aspect. Refund of Security Deposit will only be made after successful maintaining of appropriate service level of the work as mentioned below:
  - > Full security deposit shall be refunded to the contractor on expiry of one year from the actual date of completion of the work.
- 5. Supplied item will be rejected if it is not as per specification or bellow standard.
- 6. The entire work must be completed within 10 days from the received of the work order.

- 7. The Board of Councillors reserves the right to accept or reject any quotation without assigning any reasons whatsoever.
- 8. Other terms and condition will be followed as per rule.
- 9. Quotation will be received upto 1-30 PM on 01.09.2023 and opening will be done at 2-30 PM on 01.09.2023
- 10. The agency or their representative may remain present at time of opening.

N.B. Recovery of 1% (one percent) Cess on Gross bills to be made as per Regulation of Employment & Conditions Service Act. 1996.

Chairperson
Beldanga Municipality

Dated . 23 08 23

Memo No. 2696 (6) 11-1 23.

Copy forwarded for information and wide publication to :-

- 1. The District Magistrate, Murshidabad.
- 2. The Sub-Divisional Officer, Berhampore, Murshidabad.
- 3. The Block Development Officer, Beldanga-1, Beldanga, Murshidabad.
- 4. The F.O., Beldanga Municipality.
- 5. The E.O., Beldanga Municipality.
- 6. IT Co-ordinator, Beldanga Municipality with request to float this Notice to the official website of Beldanga Municipality (www. municipalitybeldanga.org).

Chairperson
Beldanga Municipality



# **Quotation**

The Chairperson,	
Beldanga Municipality.	

Name of Work Tendered	Amount Put to Tender	Rate Quoted by the Bidder (% above or less or at par)	Tendered Amount (Contract Price both in words & figures)		
	7				

17	C :41	C 11-
Yours	Taitr	ituity

Date:

To,

Signature of Participant with stamp (if any)

#### Beldanga Municipality Murshidabad

SI. No.	Description of items	Unit	Quantity	Rate	Amount
1	Brick work with 1st class bricks in cement mortar (1:6)			*	
	(a) In foundation and plinth			15	
	Building works PWD (WB), Page -15, Item - 8	m3	7.00	4882.70	34178.90
2	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor		п		
	Building works PWD (WB), Page -16, Item - 16	m2	40.000	669.48	26779.20
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]  (i) With 1:6 cement mortar (c) 15 mm thick plaster				
	Building works PWD (WB), Page -189,Item - 1	m2	100.000	139.53	13953.00
4	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc.  NOTE:Cement 0.152 cu.m per100 sq.m				
. `	Building works PWD (WB), Page -192,Item - 15	m2	100.000	32.75	3275.00

78186.10

Add @ 18% for GST = 14073.50,

92259.60

Add @1% for CESS = 922.60

93182.19

Add @ 3% for Contingency 2345.58

TOTAL = 95527.7

Say Rs.95,528.00/-

( Rupees ninety five thousand five hundred twenty eight ) only

VETTED

The estimate vetted by me accordingly by the B.O.C meeting 22 dated 27/06/2023

Beldanga Municipality

Beldanga Municipality

Chairperson Beldanga Municipality

## Beldanga Municipality Mursidabad

Repairing of Bituminous Road on emergency basis near flower mill of Lalu Ganai on Madda bituminous road, ward no - 13 within Beldanga Municipality.

Length = 225.0mtrs, Breadth = 1.50 mtrs.(avg)

	th = 225.0mtrs. Breadth = 1.50 mtrs.(avg)		l		
il. o.	Description of Item	Unit	Quantity	Rate	Amount
1	Labour for picking up existing metalled road surface to a specified average depth, including screening and stacking the pavement materials.				
	Road Works,PWD (WB),Page - 331,Item - 18.01/c/ii				
	(a) For average depth up to 40 mm by manual	-			3 .2
	means: Brick / Jhama metal surface				
	225.000 m x 1.500 m <del>x 1</del> = 337.500 m2	m2	337.500	9.50	3206.25
	Providing, laying, spreading and compacting stone aggregates of specific sizes to				1
	water bound macadam specification including spreading in uniform thickness,		1		8
	hand packing, rolling with vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding	-		n n	
	materials to fill up the interstices of coarse aggregate, watering including lighting,				,
	guarding, barricading and making necessary earthen bundh of one metre width			East a s	
	on each side and preparing the bed by necessary cutting or filling, including cost		2	9E KO	u = 5
	of all materials and hire and labour charges of all men and machinery and compacting to the required density, as per Clause 404 of Specifications for Road &				
	Bridge Works of MoRT&H (5th Revision).				
					8 80 8
	(b) Using 1.21m3 of Grading-II Aggregate (53 mm to 22.4 mm) and 0.24m3 of Stone Screening Type B (11.2 mm):-		1/2		
	Manual means				64903
	225.000 m x 1.500 m x 0.075 m = 25.313 m3	m3	25.313	2564.02	64901.70
	Providing and applying primer coat with Cationic Bitumen Emulsion of approved			/	
	grade conforming to IS: 8887-1978 and requisite quantity on prepared surface of				
	granular base including cleaning of road surface and spraying primer using				
	Mechanical means including cost and carriage of bitumen emulsion and all other incidental costs of work complete as per Clause 502 of Specifications for Road &				
	Bridge Works of MoRT&H (5th Revision).				=
	For WBM Surface: (with primer @0.85 kg/sqm)	-	8		
	5 1 14 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1			
	Road Works,PWD (WB),Page - 251,Item -5.01	l			

79292.76 792940

Add @18% for GST =

14272.69 14,2729 93565.45 93566.97

Add @ 1% foe CESS =

935.65 935,66

94501.10 94,502.6

Add @ 3% for Contingency =

2378.78 2807.00

96879.88 973096 TOTAL = Say Rs.96,880.00

(Rupees ninety six thousand eight hundred eighty) only.

**Beldanga Municipality** 

**Beldanga Municipality**